

Annex 1 to the Terms and Conditions for Use of the Service Facilities (NBS)

of

TriCon Container-Terminal Nürnberg GmbH

Description of the Infrastructure (System Sketch)

Description of the Infrastructure (System Sketch)

1. Crane (Transshipment Rail - Road)

Crane			Loading Gear	Payload (t)		Length (m)	Transshipment Possibilities					
No.	Module	Slewing Gear		Swivel Pins	Gripping Jaws		Gripping Jaws	20'	30'	40' 45' PW	Semi-trailer	Swap Body
1	1	✗	Combined gripping jaws - spreader	41	41	3.6	✗	✗	✗ ¹	✗	✗	✗
2	1	✗	Combined gripping jaws - spreader	41	41	3.6	✗	✗	✗	✗	✗	✗
3	2	✗	Combined gripping jaws - spreader	41	41	3.6	✗	✗	✗	✗	✗	✗
4	2	✗	Combined gripping jaws - spreader	41	41	3.6	✗	✗	✗	✗	✗	✗

2. Mobile Equipment (waterside transshipment)

Mobile Equipment		Loading Gear	Payload (t)		Length (m)	Transshipment Possibilities					
No.	Total craneable quay length		Swivel Pins	Gripping Jaws		Gripping Jaws	20'	30'	40'	Semi-trailer	Swap Body
1	2x 110 m	Spreader	45		-	✗	✗	✗			

¹ Transshipment from 45' PW not possible

3. Transshipment Tracks (System Sketch)

The location and designation of the transshipment tracks can be seen in the following system sketch:



